

# DTT Magnet system & Cryosystem

## DTT industry day

*Villa Mondragone, Monte Porzio Catone (Rome), Italy – 14/12/2018*

**G.M. Polli on behalf of the DTT team**



```
1101 0110 1100  
0101 0010 1101  
0001 0110 1110  
1101 0010 1101  
1111 1010 0000
```



# Outline

## Magnet system:

- Superconducting & Copper Strands
- TF coils:
  - Conductors
  - Winding packs
  - Casing structure
  - Intergration
  - Testing
- CS coils:
  - Winding
  - Assembly
- PF coils

## Cryosystem:

- Cryoplant
- Current leads
- Current leads boxes
- Feeders & cryodistribution inside cryostat

# Magnet system: requirements and overview

## Requirements:

- Flexibility for plasma shaping
- 6 T on plasma @ 2.11 m radius
- Ripple < 0.3%
- Pulse length ~ 100 s
- Mature technology for schedule constraint

## Overview:

- 18 TF coils in Nb<sub>3</sub>Sn
- 6 independent CS coils with conductor grading in Nb<sub>3</sub>Sn
- 4 independent PF coils in NbTi
- 2 independent PF coils in Nb<sub>3</sub>Sn
- 4 independent in-vessel divertor coils (Cu)
- 2 independent in-vessel coils (Cu) for vertical stabilization

# Magnet systems: reference parameters

## 18 Toroidal Field coils

**Nb<sub>3</sub>Sn** Cable-In-Conduit Conductors

6 *Double-Pancakes* (4 regular + 2 side)

$B_{\max} = 11.7 \text{ T}$

$I_{\text{op}} = 26.9 \text{ kA}$

$\Delta T_{\text{margin}} > 1.6 \text{ K}$

## 6 Central Solenoid module coils

**Nb<sub>3</sub>Sn** Cable-In-Conduit graded Conductors

*Layer Wound* (3 sections)

$B_{\max} = 14 \text{ T}, 12 \text{ T}, 8.2 \text{ T}$

$I_{\text{op-max}} = 28 \text{ kA}$

$\Delta T_{\text{margin}} > 1 \text{ K}$

## 6 Poloidal Field coils

**4 NbTi** Cable-In-Conduit Conductors


**2 Nb<sub>3</sub>Sn** Cable-In-Conduit Conductors

*Double-Pancakes* winding

$B_{\max} = 2.5 - 7.5 \text{ T}$

$I_{\text{op-max}} = 11 - 29 \text{ kA}$

$\Delta T_{\text{margin}} > 1.6 \text{ K}$  in all coils



# Superconducting & Copper Strands

## Nb<sub>3</sub>Sn:

Diameter =  $0.82 \pm 0.005$  mm, Cu:non-Cu =  $1.00 \pm 0.05$ , Cr coating =  $2 \pm 1$   $\mu$ m


Hi-Grade operative conditions:  $I_c$  (6.2K, 12T, -0.6% applied strain)  $\geq 80$  A

Hi-Grade performance at 4.2K:  $I_c$  (4.2K, 12T, 0.0% applied strain(\*) )  $\geq 290$  A

RRR: > 100

**46 tons FOR TFC + 13 tons FOR CS + 9 tons FOR PF1/6 (> 13'800 km)**

0.82 mm




## NbTi:

$0.82 \pm 0.005$  mm, Cu:non-Cu =  $1.90 \pm 0.05$ , Ni coating =  $2 \pm 1$   $\mu$ m

Required Performance at 4.2K:  $I_c$  (4.2K, 5T)  $\geq 500$  A

RRR: > 100

**32 tons FOR PF2/3/4/5 (> 6'400 km)**




## Cu:

$0.82 \pm 0.005$  mm, Cr/Ni coating =  $2 \pm 1$   $\mu$ m

RRR: > 300

**35 tons FOR TFC & CS & PF1/6 + 20 tons FOR PF (> 10'900 km)**



# TF coils: overview

$I_{op}$ : 26.92 kA


$B_{max}$ : 11.7 T

$\Delta T_{margin} > 1.6$  K

20 tons (each TFC)

## Procurements:

- $Nb_3Sn$  & Cu (Cr plated) strands
- TFC cabling & jacketing
- TFC WP
- TFC casing
- TFC in-casing integration
- TFC testing in cryogenics
- TFC assembling



# TF coils: Conductors


Conductors & Strand manufacturing schedule: 3.5 years from kick-off-meeting, **2 sets of UL every 2.5 months**

## Main features:

- External dimensions:  $24.1 \times 17.2 \text{ mm}$
- Jacket thickness:  $1.9 \text{ mm}$
- Cable:  $300 \text{ Nb}_3\text{Sn}$  and  $54 \text{ Cu}$  strands
- $0.82 \text{ mm}$  ITER-like  $\text{Nb}_3\text{Sn}$  strands (*slightly enhanced*)
- Cable pattern:  $3 \times 4 \times 5 \times 5 + 3 \times 3 \times 6 \text{ Cu}$  core
- Unit length (UL):  $270 \text{ m}$  (regular),  $190 \text{ m}$  (lateral)
- Total # of ULs:  $72$  (regular) +  $36$  (lateral) +  $8$  spare

## Key issues:

- $316 \text{ LN}$  jacket (samples and dummies to be provided in advance for winding test)
- $100\%$  welds testing
- He leak testing (pressure, flow)
- Jacketing line  $\sim 880 \text{ m}$  (for CS & PF)



# TF coils: Winding Packs (WP)

TF WP manufacturing schedule: 4.25 years from kick-off-meeting, **~1 DP every week**

4 rDPs (regular Double-Pancakes)  
2 sDPs (side Double Pancakes)

Max. hydraulic length: 135m


# turns: 130

~ 5 tons

Key issues:

- **Double pancakes (DP) winding is in the critical path (multiple shifts and/or multiple lines expected)**

- Heat treatment
- Insulation after heat treatment
- Internal joint (<2nOhm)
- Vacuum pressure impregnation (VPI)
- High shear strength on insulation
- Tight tolerance on current line ( $\phi < 2 \text{ mm}$ ) -> laser
- High voltage DC tests in vacuum (Paschen proof) ->



**ITER TF joints: The twin box concept**

*Courtesy of KStar*

Developed at CEA Cadarache through R&D on single strands, subsize and full size conductor samples



# TF coils: casing

TF casing manufacturing schedule: 4 years from kick-off-meeting, 1 casing every ~ 3 months

~ 15 tons


Max thickness: ~ 90 mm

Support structures for PF included

Outer Intercoil structures included

Key issues:

- 316LN
- 100% welds control
- Dimensional controls with laser track
- KSTAR solution envisaged
- Channels for cooling machined inside and sealed



# TF coils: integration

TF casing integration schedule: 4.25 years from kick-off-meeting, 6 months per TFC from WP & casing available

Main features:

- WP insertion into casing
- Casing welding
- Embedding impregnation
- Mechanical final machining
- He cooling piping insertion
- Final acceptance tests

Key issues:

- High voltage DC tests in vacuum (Paschen proof)
- Electrical breakers
- 316LN
- 100% welds control
- Final machining for tolerance
- Piping insulation
- Electrical terminations





# TF coils: testing

TF cryogenic testing schedule: 4 years from kick-off-meeting, ~ 2 month per TFC including coil preparation (2 weeks), cool-down (1 week), testing (1 week), warm-up (1 week), coil release (2 weeks)

Key issues:

- High voltage DC tests in vacuum at Cryogenic
- 4,5 K, 6 bar, nominal current
- Quench test
- Insulation resistance test
- Joint resistance test ( $< 2$  nOhm)



# Outline

## Magnet system:

- Superconducting & Copper Strands
- TF coils:
  - Conductors
  - Winding packs
  - Casing structure
  - Intergration
  - Testing
- CS coils:
  - Winding
  - Assembly
- PF coils

## Cryosystem:

- Cryoplant
- Current leads
- Current leads boxes
- Feeders & cryodistribution inside cryostat

# CS coils: overview

$I_{op}$ : 28 kA


$B_{max}$ : 14.0 T

$\Delta T_{margin} > 1.1$  K

**51 tons (whole solenoid)**

Procurements:

- $Nb_3Sn$ , Cu (Cr plated) strands
- CS cabling & jacketing
- CS module manufacture
- CS testing in cryogenics
- CS pre-assembling
- CS assembling




# CS coils: CS modules

CS module manufacturing schedule: 3 years  
from kick-off-meeting, **1 module every 3 months**

Coil height ~ 0,9 m  
Coil inner diameter ~ 0,8 m  
Coil outer diameter ~ 1,5 m  
Mass ~ 7 tons

## Key issues:

- **Layer wound solution with conductor grading (3 grades)**
- Insulation before heat treatment (only glass)
- Embedded joints between layers
- Vacuum pressure impregnation
- High voltage DC tests in vacuum (Paschen proof)
- Tight tolerance on current line diameter and center axis
- Cycling loading conditions (> 30000 cycles)





# CS coils: CS assembly

CS module assembling schedule: 2.25 years from kick-off-meeting (including pre-assembly)

## Key issues:

- Tight tolerance on center axis during pre-assembly
- **Assembly possible only after TF & PF magnet system completed**
- Total mass ~ 51 tons
- Total height > 6 m



# PF coils: overview

$I_{opmax}$ : 28.6 kA

$B_{max}$ : 5.9 T


$\Delta T_{margin} > 1.6$  K

PF1/2/5/6 ~ 20 tons each

PF3/4 ~ 33 tons each

## Procurements:

- $Nb_3Sn$ , NbTi, Cu (Ni plated) strands
- PF cabling & jacketing
- PF Winding
- PF testing in cryogenics (only PF1/6)
- PF pre-assembling
- PF assembling





# PF coils: PF winding

PF winding manufacturing schedule: 4.25 years from kick-off-meeting

## PF1/PF6:


- Coil height ~ 590 mm
- Inner diameter ~ 2,3 m
- Outer diameter ~ 3.4 m
- Mass ~ 20 tons
- Double pancakes 9

## PF2/PF5:

- Coil height ~ 500 mm
- Inner diameter ~ 6 m
- Outer diameter ~ 6,6 m
- Mass ~ 20 tons
- Double pancakes 8

## PF3/PF4:

- Coil height ~ 590 mm
- Inner diameter ~ 8,2 m
- Outer diameter ~ 9 m
- Mass ~ 33 tons
- Double pancakes 7



# Outline

## **Magnet system:**

- Superconducting & Copper Strands
- TF coils:
  - Conductors
  - Casing
  - Intergration
  - Testing
- CS coils:
  - Winding
  - Assembly
- PF coils

## **Cryosystem:**

- Cryoplant
- Current leads
- Current leads boxes
- Feeders & cryodistribution inside cryostat

# Cryogenic system: requirements and overview

## Requirements:

The Cryogenic System of the DTT has to provide adequate cooling during 100 s plasma pulses with full nuclear heating, repeated every 3600 s to:

- 18 TF coils + 6 current leads + Feeders;
- 6 CS module coils + 12 current leads + Feeders;
- 6 PF coils + 12 current leads + Feeders;
- Thermal shields (TS);
- Cryo-lines;
- Cryogenic pumps (under evaluation) ➡ 3.7 K

## Overview:

- **Cryopant ~ 10 kW cooling power @ 4.2 K**
- HTS Current leads (cooled @ 50K)
- Cryodistribution inside cryostat

# Cryogenic system: cryoplant system architecture

## 6 storage vessels (one for quench recovery)

- $\varnothing$  4 m  $\times$  21 m, 250 m<sup>3</sup>, 70 tons
- RT, total He content 3,6 tons

## 8 screw compressors (housed in 4 skids)

operating in parallel, oil and gas coolers, dryer

- 4,5 m  $\times$  2 m  $\times$  2,5 m, 10 tons
- Electrical parameters (2,4 MW)
- Hydraulic properties (RT, 680 g/s, 1,6 MPa)


## Refrigeration Cold Box – with LN<sub>2</sub> pre-cooling stage, 3 turbo-expanders, heat exchangers, dual 80 K and single 20 K adsorbers

- $\varnothing$  3,2 m  $\times$  12 m, 65 tons

## Auxiliary Cold Box – with baths at 4,3 K (7m<sup>3</sup>) and 3,6 K (1 m<sup>3</sup>), 2 cold circulators for 2 distinct loops, 1 cold compressor, and heat exchangers

- $\varnothing$  3,2 m  $\times$  11 m, 50 tons

*Courtesy of JT-60SA*



# Cryogenic system: cryoplant requirements


Temperature level (K)	Heat source	Average Power (W)		Equivalent power @ 4,2 K (W)	
		Normal operation (POS+DWE)	Baking mode (BAK)	Normal operation (POS+DWE)	Baking mode (BAK)
80	TS, CP baffles, cryo-distribution	45.000	135.000 <sup>(*)</sup>	~2.400	~7.100
50	HTS-CL & feeders (TF+CS+PF) <sup>(*)</sup>	33	0	~3	0
4,5	TF, CS, PF (WP, casing, distribution)	3.000	3.200	3.000	3.200
3,7	Cryo-pump panels <sup>(*)</sup>	84	0	84	0
<b>Total equivalent power @ 4.2 K (W)</b>				<b>5.484</b>	<b>10.305</b>

<sup>(\*)</sup> Data from JT60-SA

- During the baking, the estimated equivalent cooling power @ 4.2 K exceeds 10 kW.
- Moreover, during Plasma Operation State (POS), the DTT cryogenic system shall have to cope with large pulsed heat loads, perhaps twice the average power in normal operation.
- The maximum required cooling power at full performance is estimated in the range of 10 to 11 kW @ 4.2 K.

# Cryogenic system: cryoplant layout in DTT site

Cryoplant procurement schedule: 4.75 years from kick-off-meeting



# Cryogenic system: HTS current leads

HTS current leads procurement schedule: 3.75 years from kick-off-meeting

TF CL:

- 6 HTS CL (due to quench protection circuit)
- ~ 30 kA
- Stationary working conditions


CS CL:

- 12 HTS CL (one pair per module)
- ~ 30 kA
- Pulsed working conditions

PF CL:

- 12 HTS CL (one pair per module)
- ~ 30 kA
- Pulsed working conditions

*Courtesy of JT-60SA*




# Cryogenic system: current leads boxes

Current leads boxes procurement schedule: 2.25 years from kick-off-meeting *Courtesy of JT-60SA*

Each current lead box will host 4/6 HTS current leads:

- TF coils will be fed from the bottom
- 3 modules of CS + PF6/PF5/PF4 from the bottom
- 3 modules of CS + PF1/PF2/PF3 from the top





# Cryogenic system: feeders inside cryostat



Feeders & cryo-distribution procurement schedule: 1.75 years from kick-off-meeting

The distribution of coolant will be possible after the magnet system has been completely assembled.


Vacuum vessel (VV) thermal shield will be assembled during VV assembly.

Cryostat thermal shield will be assembled before cryostat closure.

Design activity is still on-going.



# Magnet system & Cryosystem: Overall schedule



QUESTIONS?



1101 0110 1100  
0101 0010 1101  
0001 0110 1110  
1101 0010 1101  
1111 1010 0000



[gianmario.polli@enea.it](mailto:gianmario.polli@enea.it)