

The material and information contained in this presentation are provided for information purposes only, and should not be construed as basis technical specifications of the call for tenders.

TFC Winding and Integration

DTT info-day on TF magnets

Aula B. Brunelli, C.R. ENEA Frascati (Rome), Italy – 08/10/2019

Presenter G. Romanelli on behalf of the DTT team




1101 0110 1100
0101 0010 1101
0001 0110 1110
1101 0010 1101
1111 1010 0000




Outline


- WP description
- Schedule
- Supply content
- WP manufacturing
- TFC integration
- Final coil preparation
- Conclusions and recommendations



WP description



- 18 TFCs;
- Nb_3Sn conductors:
 - 3x rDP (i.e. 9+9 layers)
 - 2x sDP (i.e. 9+4 layers)




rDP = regular Double Pancake
sDP = side Double Pancake

Schedule

- WP winding procedure qualification by Dec 2020;
- First WP by Sep 2021;
- First TFC by May 2022;
- 6 TFCs by Dec 2022;
- 18 TFCs by Feb 2024.

WP = Winding pack

TFC = Toroidal Field Coil



Supply content

Dummy Spools

- 1x dummy:
 - Copper cable;
 - 232 m (i.e. 222 m complete conductor + 5 m empty jacket head + 5 m empty jacket tail);
 - Single layer wound (spool diameter > 2.3 m);
 - For qualification procedures + manufacturing 1x resistive sDP.
- 1x super-dummy:
 - Nb₃Sn cable;
 - 170 m (i.e. 160 m complete conductor + 5 m empty jacket head + 5 m empty jacket tail);
 - Single layer wound (spool diameter > 2.3 m);
 - For manufacturing 1x superconductive sDP

Supply content

Regular Spools

- 54x rDP:
 - SC cable;
 - 232 m (i.e. 222 m complete conductor + 5 m empty jacket head + 5 m empty jacket tail);
 - Single layer wound (spool diameter > 2.3 m);
- 36x sDP:
 - SC cable;
 - 170 m (i.e. 160 m complete conductor + 5 m empty jacket head + 5 m empty jacket tail);
 - Single layer wound (spool diameter > 2.3 m).

Supply content

Casing structure (Stainless Steel AISI 316LN)


- 18x Casing structure components to be assembled and welded;
- 1 m inboard leg mockup for integration and welding qualification;
- Inboard-outboard-interface mockup for welding qualification




WP manufacturing

Operations to complete x18 WPs

1. 3x rDP and 2x sDP winding;
2. He inlet welding;
3. Internal and terminal joint preparation;
4. Nb₃Sn heat-treatment;
5. Turn insulation application;
6. DP insulation application;
7. DPs stacking;
8. Inter-DP and terminal joint finalization;
9. Ground insulation application;
10. VPI and curing.



WP manufacturing – DP winding




Preliminary actions:

- Review unit-length transportation conformity;
- Visual inspection;
- Nitrogen flow and Helium leak test.

Operations:

- Inline clean and sandblast the conductor surface;
- Wind 3x rDP;
- Wind 2x sDP.

WP manufacturing – He inlet welding




Preliminary actions:


- Weld mockup preparation;
- Non-destructive inspection on mockups;
- Helium leak test on mockups.

Operations:

- Machine jacket opening to fit He inlet;
- Weld 1x He inlet for each DP;
- Perform non-destructive inspection of all inlets;
- Perform Helium leak test on all inlets.



WP manufacturing – Internal and terminal joint preparation




Preliminary actions:

- 1x inter-DP + 2x terminal joint mockup preparation;
- Mockup shipment to ENEA for qualification purposes.

Operations:


- Finalize 1x inter-DP joint box for each DP;
- Finalize 1x terminal joint box for each DP.

WP manufacturing – Nb₃Sn heat treatment



Operations:


- Perform the Nb₃Sn heat treatment.



WP manufacturing – turn insulation application

Preliminary actions:

- Longitudinal strain on the SC assessment (must be within $-0.8\% \div 0.2\%$ and an additional equivalent strain $-0.5\% \div -0.3\%$ due to heat treatment must be considered);
- Mechanical and electrical performance assessment on mockups.



ENEA assessment:

$$\Delta H = 0.7 \text{ m}$$


$$L = 15 \text{ m}$$

$$\epsilon_{x_max} = 0.1\%$$

Operations:

- Apply 1 mm of E-glass fiber;
- Perform visual inspection of all DPs to check dimensions;
- Verify electrical integrity;
- Verify each DP centerline position.


WP manufacturing – DP insulation application + DP stacking



Operations:

- Apply 0.5 mm of E-glass fiber;
- Verify space allowances and positioning tolerance are met (i.e. general class medium tolerances required);
- Align inter-DP joint boxes;
- Verify electrical integrity;
- Verify WP centerline position.



WP manufacturing – DP insulation application + DP stacking



Operations:

- Apply 0.5 mm of E-glass fiber;
- Verify space allowances and positioning tolerance are met (i.e. general class medium tolerances required);
- Align inter-DP joint boxes;
- Verify electrical integrity;
- Verify WP centerline position.

WP manufacturing - Inter-DP and terminal joint finalization



Operations:

- Finalize Inter-DP and termination twin-box joints;
- Verify space allowances are met;
- Perform Nitrogen flow and Helium leak tests;
- Verify the final arrangement is Paschen-proof.


WP manufacturing - Ground insulation application + VPI and curing

Preliminary actions:

- Mechanical and electrical performance assessment on mockups;
- Perform Helium leak tests before and after impregnation;
- Perform Paschen test at 3 kV before and after impregnation.

Operations:


- Add filler material where necessary;
- Apply 2 mm overlapped layers of E-glass fiber and Kapton;
- VPI & curing of the insulation system;
- Apply a conductive finish on the external surface of the WP;
- Apply detaching agents on the external surface of the WP;
- Verify WP centreline position.



TFC integration

Operations to complete x18 TFCs

1. Casing integration and welding;
2. He piping inlet and outlet termination;
3. Surface finish;
4. Bolt holes preparation;
5. Final coil preparation.




TFC Integration – Casing integration and welding

Preliminary actions:


- Complete 1 m long WP mockup embedding inside 1 m long inboard leg mockup;
- Perform welding of 1 mockup of the Inboard-outboard-interface mockup.

Operations:

- Integrate 4 mm E-glass fiber as filler material;
- Embed the WP;
- Perform all welds;
- Perform non destructive tests on welds;
- Perform in-case impregnation & curing of filler material.




TFC Integration – Casing integration and welding



Operations:

- Verify all tolerances are met;
- Verify relative position between inboard and outboard leg;
- Verify WP centerline position.

TFC Integration – He piping inlet and outlet termination + breaker installation





Operations:

- Complete installation of Helium piping;
- Integrate the electric breaker to the terminations;
- Perform Helium leak test of all TFCs;
- Perform Paschen test at 3 kV of all TFCs.


TFC Integration – Surface finish + bolt holes preparation

Operations:

- Finish the external surface of the TFCs for the assembly process;
- Drill holes for the installation of inter-coil structure bolts and leave material in excess to recover alignment tolerances during the assembly.




TFC Integration – final coil preparation




Operations:

- Prepare support structures to protect He-piping, inter-DP and termination joints during transport;
- Prepare the insulation plate to electrically insulate TFCs on the wedge;
- Prepare the transport jig for each TFC.



Conclusions & Recommendations

- 6 TFCs shall be completed by 2022;
- 3 complete TFCs shall be shipped to ENEA by 2022;
- All dimensions and tolerances included in this presentation will be subjected to review before being officially published in the Technical Specifications.



QUESTIONS?



1101 0110 1100
0101 0010 1101
0001 0110 1110
1101 0010 1101
1111 1010 0000



gherardo.romanelli@enea.it